



DEPARTMENT OF PUBLIC WORKS

Quality, Excellence, Innovation

Christopher Blunk, P.E.
DIRECTOR

July 9, 2026

Administration
PO Box 4186
San Rafael, CA 94913-4186
415 473 6528T
415 473 3799 F
415 473 3232 TTY
CRS Dial 711
www.marincounty.org/pw

To: All holders of CONTRACT DOCUMENTS for:

Green Stormwater Infrastructure Project – Phase 1 County Project No. 41GSI2301

From: Liza DeFrain
Senior Stormwater Planner
Department of Public Works

Re: Addendum 2

You are hereby advised of the following revisions and/or clarifications to said Contract Documents:

SPECIFICATIONS:

1. Add the following to the ninth paragraph of the Notice to Bidders on page 9:

It is acceptable for a subcontractor to hold the C27 license in lieu of the prime contractor.

Remove page 9 and replace with page 9 [Addendum 2] included with this addendum.

2. Replace the tenth paragraph on page 131 of the General Provisions with the following:

1. Shall transport it to a Class II landfill appropriately permitted to receive the material.

Remove page 131 and replace with page 131 [Addendum 2] included with this addendum.

3. Replace the first paragraph under Section “19-1.04 Payment” on page 189 of the Technical Specifications with the following:

The contract price paid per Cubic Yard for EARTHWORK & GRADING shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in earthwork and grading, including exporting soil to a Class II landfill and importing soil to meet finish grades (if necessary), compaction, scarifying soil and fine grading, and all other work related to excavation, grading, earthwork, dewatering and demolition, temporary protection at existing utilities with shallow cover during construction,

Accounting

Administrative Services

Airport

Building Maintenance

Capital Projects

Certified Unified Program
Agency (CUPA)

Communications
Maintenance

Disability Access

Engineering & Survey

Fleet Operations

Flood Control &
Water Resources

Land Development

Procurement

Real Estate

Reprographic Services

Road Maintenance

Stormwater Program

Transportation &
Traffic Operations

Waste Management

ditch excavation for inflow and outflow areas, complete in place, as shown on the plans, as specified in the Standard Specifications, the Special Provisions and these Technical Specifications, and as directed by the County Engineer.

Remove page 189 and replace with page 189 [Addendum 2] included with this addendum.

PLANS:

1. Replace Note 5 on Sheet 3 of the Plans with the following:

CONTRACTOR TO LAY OUT PLANTS FOR APPROVAL PRIOR TO INSTALLATION. LANDSCAPE ARCHITECT TO INSPECT PLANTING LAYOUT PRIOR TO HOLE EXCAVATION AND PLANT INSTALLATION.

Remove Sheet 3 and replace with Sheet 3 [Addendum 2] included with this addendum.

2. Add the following Notes to Detail 1 on Sheet 16 of the Plans:
 3. CONTRACTOR SHALL SUBMIT FLAGSTONE SAMPLE TO COUNTY FOR APPROVAL.
 4. CONTRACTOR SHALL ROUND THE EDGES OF THE SPLASH PAD TO FORM A SEMI-CIRCULAR SHAPE. PROVIDE SHOP DRAWINGS FOR COUNTY APPROVAL.

Remove Sheet 16 and replace with Sheet 16 [Addendum 2] included with this addendum.

Enclosed:

- Specifications
 - Page 9 [Addendum 2]
 - Page 131 [Addendum 2]
 - Page 189 [Addendum 2]
- Plans
 - Sheet 3 [Addendum 2]
 - Sheet 16 [Addendum 2]

END OF ADDENDUM NO. 2

Approved by and issued by:

Robin Bartlett

Robin Bartlett
Interim Assistant Director of Public Works
County of Marin

**MARIN COUNTY DEPARTMENT OF PUBLIC WORKS
SAN RAFAEL, CALIFORNIA**

NOTICE TO BIDDERS

INVITING SEALED PROPOSALS OF BIDS

Project Name: Civic Center Green Stormwater Infrastructure Project- Phase 1
County Project No. 41GSI2301

Bids for this Project must be submitted online via BidExpress by **Thursday July 16, 2026 at 2:00 p.m.** at which time they will be publicly opened and read via Zoom
<https://us05web.zoom.us/j/85891795277?pwd=BS5qBHHNvnWcgS3MKsnfCV0eU3rFNI.1>

Meeting ID: 858 9179 5277
Passcode: DPWSWG2026

The Civic Center Green Stormwater Infrastructure Project is a multi-phase project to build green stormwater infrastructure to treat many of the campus parking lots. The current project being advertised is Phase 1 which includes construction of two bioretention systems adjacent to the Civic Center “panhandle” parking lot located south of the Marin County Corporation Yard (4 Peter Behr Dr. San Rafael, CA 94903).

The bid package, plans, and specifications may be viewed at:
<https://www.bidexpress.com/businesses/53528/home>.

There is a mandatory pre-bid conference scheduled for this project on **July 1, 2026 at 10:00 a.m.** at the Civic Center Campus, 3501 Civic Center Dr. Bidders shall meet at the “panhandle” parking lot south of the Civic Center Corporation Yard, which is located at 4 Peter Behr Dr. San Rafael, CA 94903. Exact location here: <https://maps.app.goo.gl/4fZ4JgYBCzTizEaPA>. A second opportunity to attend the mandatory pre-bid conference is scheduled for **Monday, July 13, 2026 at 3:00 p.m.** at the Civic Center Campus, 3501 Civic Center Dr. Bidders shall meet at the “panhandle” parking lot south of the Civic Center Corporation Yard, which is located at 4 Peter Behr Dr. San Rafael, CA 94903. Exact location here: <https://maps.app.goo.gl/4fZ4JgYBCzTizEaPA>

The Engineer’s estimate for this project is \$500,000.

The Working Days for this project are 50 days.

Bidder shall possess a valid Class A and a C27 license at the time of bid submittal. It is acceptable for a subcontractor to hold the C27 license in lieu of the prime contractor.

All bids must include a bid security for at least ten percent (10%) of the base bid, in the form of cash, certified or cashier’s check, or bidder’s bond.

Contractor shall submit the lead compliance plan as an informational submittal.

Before starting any activity that presents the potential for lead exposure to employees who have no prior training, including State employees, Contractor shall provide a safety training program to these employees that complies with 8 CA Code of Regs § 1532.1 and Contractor's lead compliance plan.

Contractor shall submit copies of air monitoring or job site inspection reports made by or under the direction of the CIH under 8 CA Code of Regs § 1532.1 within ten (10) days after the date of monitoring or inspection.

Contractor shall supply personal protective equipment, training, and washing facilities required by Contractor's lead compliance plan for State employees.

2. Unregulated Earth Material Containing Lead

If unregulated material is disposed of, Contractor:

1. Shall submit at least fifteen (15) days before disposal, the form titled "Agreement between a Contractor Working on State Facilities and a Real Property Owner for Disposing Construction-related Material Suitable for Use on Residential Zoned Property" which discloses the lead concentration of the material to the receiving property owner and obtains authorization for disposal on the property, and give a copy of the signed form to the property owner.
2. Is responsible for any additional sampling and analysis required by the receiving property owner.

If Contractor chooses to dispose of unregulated material at a commercial landfill, Contractor:

1. Shall transport it to a Class II landfill appropriately permitted to receive the material
2. Is responsible for identifying the appropriately permitted landfill to receive the material and for all associated trucking and disposal costs, including any additional sampling and analysis required by the receiving landfill

7-1.02L. Public Contract Code

1. Antitrust Claims

In entering into a public works contract or a subcontract to supply goods, services, or materials pursuant to a public works contract, the Contractor or subcontractor offers and agrees to assign to the awarding body all rights, title, and interest in and to all causes of action it may have under section 4 of the Clayton Act (15 U.S.C. Sec. 15) or under the Cartwright Act (Chapter 2 (commencing with § 16700) of Part 2 of Division 7 of the Business and Professions Code), arising from purchases of goods, services, or materials pursuant to the public works contract or the subcontract. This assignment shall be made and become effective at the time the awarding

15-1.04 Payment

The contract price paid per Linear Foot for REMOVE CONCRETE CURB, CURB & GUTTER AND BASE shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in sawcutting, removal of concrete curb, curb & gutter and base, including removal, transport and disposal of the concrete and steel, as shown on plans, as specified in the Standard Specifications and these Special Provisions, and as directed by the Engineer.

The contract price paid per Square Foot for SAWCUT AND REMOVE AC PAVING AND BASE shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in removing asphalt paving and base, including sawcutting, removal of subsoils to design grades, off-haul and disposal of asphalt paving and base material, complete in place as shown on the plans, as specified in the Standard Specifications, the Special Conditions and these Technical Specifications, and as directed by the County Engineer.

[illegible]

DIVISION III EARTHWORK AND LANDSCAPE

17 GENERAL

Replace section 17-2.04 with:

17-2.04 Payment

The contract Lump Sum price paid for CLEARING AND GRUBBING shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in clearing and grubbing, including the removal and disposal of all resulting material, as shown on the plans, as specified in the Standard Specifications and these Special Provisions, and as directed by the Engineer.

19 EARTHWORK

Replace section 19-1.04 with:

19-1.04 Payment

The contract price paid per Cubic Yard for EARTHWORK & GRADING shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in earthwork and grading, including exporting soil to a Class II landfill and importing soil to meet finish grades (if necessary), compaction, scarifying soil and fine grading, and all other work related to excavation, grading, earthwork, dewatering and demolition, temporary protection at existing utilities with shallow cover during construction, ditch excavation for inflow and outflow areas, complete in place, as shown on the plans, as specified in the Standard Specifications, the Special Provisions and these Technical Specifications, and as directed by the County Engineer.

The bid quantity is a Final Pay Quantity. The final pay quantity for EARTHWORK & GRADING will not be adjusted as specified in Section 9-1.02C, "Final Pay Item Quantities" of the State Standard Specifications if the excavation limit are not changed by the Engineer.

